

3.4.2 "Typical" Construction Waste Estimated for a 2,000-Square-Foot Home (1)

<u>Material</u>	<u>Weight</u>		<u>Volume (cu. yd.) (2)</u>
	<u>(pounds)</u>	<u>(percent)</u>	
Solid sawn wood	1,600	20%	6
Engineered wood	1,400	18%	5
Drywall	2,000	25%	6
Cardboard (OCC)	600	8%	20
Metals	150	2%	1
Vinyl (PVC) (3)	150	2%	1
Masonry (4)	1,000	13%	1
Hazardous Materials	50	1%	-
<u>Other</u>	<u>1,050</u>	<u>13%</u>	<u>11</u>
Total	8,000	100%	50

Note(s): 1) See Table 2.1.7 for materials used in the construction of a new single-family home. 2) Volumes are highly variable due to compressibility and captured air space in waste materials. 3) Assuming 3 sides of exterior clad in vinyl siding. 4) Assuming a brick veneer on home's front facade.

Source(s): NAHB's Internet Home Page, Residential Construction Waste: From Disposal to Management, Oct. 1996.